



# CANVASBACK VAULT TOILET

SHEET INDEX				
Sheet #	Sheet Name	Revision	Description	Rev. Date
0.00	COVERSHEET			
1.00	FLOOR PLAN, OPENINGS, & DETAILS			
1.01	DETAILS			
2.00	PANEL LAYOUT & ROOF SECTION			
4.00	EXTERIOR ELEVATIONS			



FRONT LEFT ISOMETRIC VIEW



RIGHT REAR ISOMETRIC VIEW

PROJECT CONTACTS:

HUFFCUTT CONCRETE PROJECT MANAGER

PROJECT GENERAL CONTRACTOR

JOBSITE ACCESS NOTES

SELLERS TRUCKS REQUIRE 50'-0" ALL WEATHER ACCESS AROUND EXTERIOR/INTERIOR OF THE BUILDING.

ACCESS AREAS SHALL BE ADEQUATE FOR UNRESTRICTED OPERATION OF SELLERS TRUCKS.

ACCESS/HAUL ROADS BY OTHERS (NOT BY HUFFCUTT CONCRETE). SELLERS TRUCKS TO OPERATE UNDER THEIR OWN POWER.

OBSTRUCTIONS, INCLUDING POWER LINES, WIRES & OBJECTS WHICH ARE HAZARDOUS TO SELLERS TRUCKS & PERSONNEL SHALL BE REMOVED BY BUYER.

DAMAGE TO EXISTING LANDSCAPING, DRIVES, SIDEWALKS, CURBS, FOUNDATIONS, SLABS, UNDERGROUND UTILITIES AND OTHER INSTALLATIONS TO FACILITATE INSTALLATION WILL NOT BE THE RESPONSIBILITY OF HUFFCUTT CONCRETE.

ABBREVIATIONS

@	-	AT	CDR	-	COTTON DUCK REINFORCED	GALV	-	HOT DIP GALVANIZE	OPNG	-	OPENING	TBRE	-	TOP OF BEAM RISER ELEV.	TRE	-	TOP OF RISER ELEV.
∅	-	DIAMETER	CONC	-	CONCRETE	GC	-	GENERAL CONTRACTOR	OPP	-	OPPOSITE	TCE	-	TOP OF COLUMN ELEV.	TTE	-	TOP OF DBL TEE ELEV. (AT GRID)
A.B.	-	ANCHOR BOLT	CONN	-	CONNECTION	INS	-	INSERT	PBE	-	PLANK BEARING ELEV.	TCWE	-	TOP OF CIP WALL ELEV.	TSE	-	TOP OF SPANDREL ELEV.
ARCH	-	ARCHITECTURAL	CONT	-	CONTINUOUS	INSUL	-	INSULATION	PROJ	-	PROJECTION	TCWP	-	TOP OF COLUMN W.P. (AT GRID)	TWE	-	TOP OF WALL ELEV.
BBE	-	BRICK BEARING ELEV.	DBE	-	DECK BEARING ELEV.	INT	-	INTERIOR	ROF	-	RANDOM ORIENTATED FIBER	TECE	-	TOP OF EXISTING COLUMN ELEV.	TYP	-	TYPICAL
BCE	-	BOT. OF COLUMN ELEV.	DIA	-	DIAMETER	JBE	-	JOIST BEARING ELEV.	REQD	-	REQUIRED	TETE	-	TOP OF EXISTING DBL TEE ELEV.	UNO	-	UNLESS NOTED OTHERWISE
BM	-	BEAM	DTBE	-	DOUBLE TEE BEARING ELEV.	JST	-	JOIST	RVL	-	REVEAL	TFE	-	TOP OF FOOTING ELEV.	W	-	WITH
BOS	-	BOT. OF STEEL	EA	-	EACH	JT	-	JOINT	SGE	-	SLAB ON GRADE ELEV.	TFWE	-	TOP OF FOUNDATION WALL ELEV.	WHE	-	WEST HAUNCH ELEVATION
(B)	-	BOTTOM	EHE	-	EAST HAUNCH ELEVATION	LLH	-	LONG LEG HORIZONTAL	SHE	-	SOUTH HAUNCH ELEVATION	TGBE	-	TOP OF GRADE BEAM ELEV.	WP	-	WORKING POINT
BOT	-	BOTTOM	ELEV	-	ELEVATION	LLV	-	LONG LEG VERTICAL	SIL	-	SUPERIMPOSED LOAD	THE	-	TOP OF HAUNCH ELEV.	WSE	-	WEST STEP ELEVATION
BPE	-	BOT. OF POCKET ELEV.	EP	-	ELECTRO- PLATED	MAX	-	MAXIMUM	SIM	-	SIMILAR	THWP	-	TOP OF HAUNCH W.P. (AT GRID)	WWF	-	WELDED WIRE FABRIC
BRG	-	BEARING	ESE	-	EAST STEP ELEVATION	MIN	-	MINIMUM	SPA	-	SPACES	TLE	-	TOP OF LEDGE ELEV.	ZRC	-	PAINTED W/ ZINC RICH COMPOUND
BSE	-	BOT. OF SPANDREL ELEV.	EXT	-	EXTERIOR	MISC	-	MISCELLANEOUS	SS	-	STAINLESS STEEL	TLWP	-	TOP OF LEDGE W.P. (AT GRID)			
BWE	-	BOT. OF WALL ELEV.	FDN	-	FOUNDATION	NHE	-	NORTH HAUNCH ELEVATION	SSE	-	SOUTH STEP ELEVATION	TOD	-	TOP OF DECK			
C/L	-	CENTERLINE	FFE	-	FINISH FLOOR ELEV.	NSE	-	NORTH STEP ELEVATION	SSBE	-	SOLID SLAB BRG ELEV.	TOS	-	TOP OF STEEL			
CIP	-	CAST IN PLACE CONCRETE	FTG	-	FOOTING	NTS	-	NOT TO SCALE	(T)	-	TOP	TPCE	-	TOP OF PRECAST ELEV.			
CANT	-	CANTILEVER	FTTE	-	FUTURE TOP DBL TEE ELEV.	O/C	-	ON CENTER	TATE	-	TOP OF ARCH TRIM ELEV.	TPE	-	TOP OF PIER ELEV.			

PRECAST PRODUCER:



Huffcut Concrete  
4154 123rd Street  
Chippewa Falls, WI 54729  
PH: (715)723-7446  
www.Huffcut.com

SIGNATURE AND SEAL

ISSUED FOR / ISSUE DATE

FOR SUBMITTAL  
DATE

CANVASBACK

PROJECT ADDRESS

COVERSHEET

SHEET TITLE:


REVISIONS

DRN BY: JS CHK BY: Checker


PROJECT NO: 1234

SHEET:

0.00



**1 FLOOR PLAN & FLOOR OPENINGS**  
1.00 3/8" = 1'-0"



**2 VAULT FLOOR PLAN**  
1.00 3/8" = 1'-0"

PRECAST PRODUCER:



Huffcut Concrete  
4154 123rd Street  
Chippewa Falls, WI 54729  
PH: (715)723-7446  
www.Huffcut.com

SIGNATURE AND SEAL

ISSUED FOR / ISSUE DATE

FOR SUBMITTAL  
DATE

CANVASBACK

PROJECT ADDRESS

FLOOR PLAN, OPENINGS, & DETAILS

SHEET TITLE:

REVISIONS

DRN BY: JS CHK BY: CL

PROJECT NO: 1234

SHEET:

1.00

